



site care information

Timber is a natural product which is affected by the extremes of weather. When exposed to rain and/or prolonged and intense sunshine, timber can warp. It is therefore important to look after timber once it arrives on site.

Taking care of IRO cladding and decking when it arrives on site will make a huge difference to its straightness when it is installed. IRO will arrive to your site packaged as follows:



- Full packs of IRO will come in the factory packaging which carries the IRO logo.
- During the summer months try to reduce the time your IRO deliveries sit in your storage compound/site.
- Upon receipt of your delivery please ensure that you have tarpaulin in stock as this may be required to cover any exposed lengths.
- Whilst it is not always possible to ensure that your storage area is flat, use bearers to ensure that packs of IRO are level.
- When stacking packs, the bearers should be positioned directly in line with the bearers below.
- Never place packs of IRO on top of loose timbers as the stack will be unstable.
- When IRO is stored outside, ensure the pack is protected in the original wrap or a tarpaulin. IRO left unprotected may be significantly affected when in direct sunlight, especially during the summer months.
- In direct sunlight it is best to turn the packs every so often, as to avoid one side facing direct sunlight for a prolonged period of time.

